



Equipped with 300SS Clamps Installation Torque 60in-lb



300 S. DAYTON ST. DAVISON, MI 48423 PH: 810-653-9626 FAX:810-654-2616

Part Weight	6.25 lbs.	TOLI
Min/Max Temp.	-30/140 Degrees F	.X= Fro
Pressure Tested	4.3 PSI	v
Material	Flexible PVC	.X AN
Installation Torque	60" Lbs.	UNLESS OTHE
Conforms to ASTM	D5926, C1173	
Box Quantity	5	INCHES
Clamps used	300 Series	

TOLERANCES: X= Fractional ±

 $.XX = \pm .02$ $.XXX = \pm .030$ $ANG. = \pm 0.5^{\circ}$ LESS OTHERWISE SPECIFIED

1002-1010

Coupling 10" Clay x 10" PVC

NOTES:
- SOME HIDDEN LINES NOT SHOWN
-BREAK ALL SHARP CORNERS
-REPORT ALL CHANGES TO

PROPRIETARY AND CONFIDENTIAL

THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF FERNCO, INC. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOUT THE WRITTEN PERMISSION OF FERNCO, INC.

3RD ANGLE PROJECTION CHECKER: 10/31/2014 DO NOT SCALE DRAWING

not to scale SHEET 1 OF 1